

**Town of Branford**  
**RFQ**  
**Main Street Reconstruction and Rehabilitation**  
**Addendum #2**

**Date:** June 1<sup>s</sup>, 2020

**Submission Date:** June 11<sup>th</sup>, 2020, remains unchanged

Prospective bidders, and all those concerned, are hereby informed that the following is made a part of the bid documents, which should be amended as follows:

The following questions were received about the bid, with answers following:

1. Can the Town please provide a copy of the LOTCIP application and corridor concept for the project?

**Conceptual plans, circulation plans, and transit plans will be compiled and shared with the selected consultant. The construction phase of the project has been approved by the South Central Regional Council of Governments for \$2.5M. LoTCIP application to the state is currently being prepared. The preliminary estimate has been attached with this Addendum.**

Respectfully submitted,

John M. Hoefflerle, PE, CFM  
Town Engineer

**Please acknowledge receipt of addendum below and submit with your bid submittal.**

**Signature:** \_\_\_\_\_ **Date:** \_\_\_\_\_

**Title:** \_\_\_\_\_

**Company:** \_\_\_\_\_

**TOWN OF BRANFORD**  
**ENGINEERING DEPARTMENT**  
**MAIN STREET RECONSTRUCTION - PRELIM ESTIMATE**  
*SOUTH MAIN STREET TO CHESTNUT STREET*

4/25/2019  
JA/JMH

<i>ITEM</i>	<i>QTY</i>		<i>UNIT PRICE</i>	<i>EXTENDED</i>
<b>CROSSWALKS</b>				
Earth Excavation - included in road excavation				
pavers for crosswalks	7887	SF	\$ 27.20	\$ 214,526.40
4" reinforced PCC base	7887	SF	\$ 8.40	\$ 66,250.80
6" processed base	146	CY	\$ 65.60	\$ 9,577.60
ADA ramps @ crosswalks	40	EACH	\$ 1,300.00	\$ 52,000.00
<b>CURBING</b>				
granite curbing straight	598	LF	\$ 56.40	\$ 33,727.20
granite curbing curved	141	LF	\$ 80.60	\$ 11,364.60
reset granite curbing	335	LF	\$ 50.00	\$ 16,750.00
<b>SIDEWALKS</b>				
concrete sidewalk removal	273	SY	\$ 69.80	\$ 19,055.40
concrete sidewalk to paver-pavers	2450	SF	\$ 27.20	\$ 66,640.00
4" reinforced PCC base	2450	SF	\$ 8.40	\$ 20,580.00
6" processed base	45.5	CY	\$ 65.60	\$ 2,984.80
concrete apron removal	37.5	SY	\$ 69.80	\$ 2,617.50
concrete apron to paver-pavers	355	SF	\$ 27.20	\$ 9,656.00
4" reinforced CC base	355	SF	\$ 8.40	\$ 2,982.00
6" processed base	6.6	CY	\$ 65.60	\$ 432.96
replace damaged pavers	44.5	SF	\$ 30.00	\$ 1,335.00
reset brick pavers	840	SF	\$ 30.00	\$ 25,200.00
stop sign	1	EACH	\$ 457.20	\$ 457.20
sign post	4	EACH	\$ 600.00	\$ 2,400.00
stop bar	10	LF	\$ 3.00	\$ 30.00
crosswalk signs	2	EACH	\$ 457.20	\$ 914.40
pedestrian signal 1 way	4	EACH	\$ 750.00	\$ 3,000.00
pedestrian signal 2 way	1	EACH	\$ 1,000.00	\$ 1,000.00
asphalt apron & patch	70	SY	\$ 50.00	\$ 3,500.00
<b>ROADWAY</b>				
EARTH EXCAVATION	5950	CY	\$ 21.00	\$ 124,950.00
AGGREGATE SUBBASE	2400	CY	\$ 45.00	\$ 108,000.00
PROCESSED AGGREGATE BASE	1830	CY	\$ 65.00	\$ 118,950.00
HMA S1.0	1875	T	\$ 120.00	\$ 225,000.00
HMA S0.375	1875	T	\$ 120.00	\$ 225,000.00
CATCHBASINS	23	EACH	\$ 4,184.20	\$ 96,236.60
MINOR ITEMS (20%)	1	LS	\$ 273,776.37	\$ 273,776.37
MOBILIZATION (7%)	1	LS	\$ 114,986.08	\$ 114,986.08
M&P OF TRAFFIC (4%)	1	LS	\$ 65,706.33	\$ 65,706.33
STAKING SERVICES (1%)	1	LS	\$ 16,426.58	\$ 16,426.58
INFLATION (4%/YEAR)	1	LS	\$ 65,706.33	\$ 65,706.33
CONTINGENCIES (10%)	1	LS	\$ 164,265.82	\$ 164,265.82
INCIDENTALS (10%)	1	LS	\$ 164,265.82	\$ 164,265.82

TOTAL \$ 2,330,251.80  
**SAY \$ 2,500,000.00**